

Monitoring Report Sheet (Input Sheet) [For Verification]

Table 1: Parameters monitored *ex post*

(a)	(b)	(c)	(d)	(e)	(f)	(g)	(h)	(i)	(j)	(k)
Monitoring period	Monitoring point No.	Parameters	Description of data	Monitored Values	Units	Monitoring option	Source of data	Measurement methods and procedures	Monitoring frequency	Other comments
20/9/2016 - 26/12/2016	1	PH _p	Net heat quantity supplied by the project HOB during the period <i>p</i> .	1,426	GJ/p	Option C	Logged data of net heat quantity supplied by the project HOB	Measurement methods which are using a heatmeter meet the industrial standards (host country or international standard). Monitoring data is the amount of heat supplied from the project HOB. This monitoring data is recorded in the data logger that is built into the heat meter. Electric data recorded on the data logger is input to the spreadsheet properly. In these monitoring activities, QA/QC be implemented. - In the case that heatmeter with verification is used, the verification validity for the heatmeter does not expire till the last date of the monitoring period. - If the heatmeter with the verification is not required in the industrial standard, uncertainty of the calibration data of the monitoring equipment meet the following conditions; - It is within accepted level of the verification. - It is within the accuracy level of industry standard requires. Required calibration frequency is the frequency which can be confirmed to be within the accuracy level of the requirement of industrial standard.	Measuring frequency: Continuously Recording frequency: Hourly	Trouble shooting procedure of missing data; Completed by the hourly minimum value (excluding abnormal value) of available recorded data during the monitoring period.
20/9/2016 - 26/12/2016	2	HMP _p	Total hours of the project HOB operation during the period <i>p</i>	4,672	hours/p	Option C	Identified by monitoring period	Total time from the start time of monitoring to the end time of monitoring	---	---

Table 2: Project-specific parameters fixed *ex ante*

(a)	(b)	(c)	(d)	(e)	(f)
Parameters	Description of data	Estimated Values	Units	Source of data	Other comments
RPC _{P,J,HOB}	Rated power consumption of the project HOB	1	kW	Catalog value provided by the manufacturer of the project HOB	
EF _{CO2,grid}	CO ₂ emission factor of the grid electricity consumed by the project HOB	1.1030	tCO ₂ /MWh	The most recent value available at the time of validation is applied and fixed for the monitoring period thereafter. The data is sourced from CDM Mongolia unless otherwise instructed by the Joint Committee.	

Table3: *Ex-post* calculation of CO₂ emission reductions

Monitoring Period	CO ₂ emission reductions	Units
20/9/2016 - 26/12/2016	23	tCO ₂ /p

[Monitoring option]

Option A	Based on public data which is measured by entities other than the project participants (Data used: publicly recognized data such as statistical data and specifications)
Option B	Based on the amount of transaction which is measured directly using measuring equipments (Data used: commercial evidence such as invoices)
Option C	Based on the actual measurement using measuring equipments (Data used: measured values)

Monitoring Report Sheet (Calculation Process Sheet) [For Verification]

1. Calculations for emission reductions	Fuel type	Value	Units	Parameter
Emission reductions during the period p	N/A	23	tCO ₂ /p	ER _p
2. Selected default values, etc.				
CO ₂ emission factor of coal	Coal	0.0909	tCO ₂ /GJ	EF _{CO₂, coal}
Boiler efficiency of the reference HOB	N/A	0.533	-	η _{RE,HOB}
Boiler efficiency of the project HOB	N/A	0.610	-	η _{PJ,HOB}
3. Calculations for reference emissions				
Reference emissions during the period p	N/A	243	tCO ₂ /p	RE _p
Reference Emissions	N/A	243	tCO ₂ /p	
Net heat quantity supplied by the project HOB	N/A	1,426	GJ/p	PH _p
Boiler efficiency of the reference HOB	N/A	0.533	-	η _{RE,HOB}
CO ₂ emission factor of coal	Coal	0.0909	tCO ₂ /GJ	EF _{CO₂, coal}
4. Calculations of the project emissions				
Project emissions during the period p	N/A	220	tCO ₂ /p	PE _p
Project emissions (Fossil fuel consumption)	N/A	213	tCO ₂ /p	
Net heat quantity supplied by the project HOB	N/A	1,426	GJ/p	PH _p
Boiler efficiency of the project HOB	N/A	0.610	-	η _{PJ,HOB}
CO ₂ emission factor of coal	Coal	0.0909	tCO ₂ /GJ	EF _{CO₂, coal}
Project emissions (Electricity consumption)	N/A	7	tCO ₂ /p	
Electricity consumption of the project HOB	Electricity	6	MWh/p	EC _p
Total hours of the project HOB operation	N/A	4,672	h/p	HMP _p
Rated power consumption of the project HOB	N/A	1	kW	RPC _{PJ,HOB}
CO ₂ emission factor of the grid	Electricity	1.1030	tCO ₂ /MWh	EF _{CO₂, grid}

[List of Default Values]

CO ₂ Emission Factor of Coal used in HOBs	EF _{CO₂, coal}	unit
Default emission factor applied to Lignite in fuel according to "2006 IPCC Guidelines for National Greenhouse Gas Inventory"	0.0909	tCO ₂ /GJ

Boiler Efficiency of coal-fired HOB in Mongolia	η	unit
Boiler Efficiency of Reference the HOB	0.533	-
Boiler Efficiency of the Project HOB	0.610	-

Monitoring Report Sheet (Input Sheet) [For Verification]**Table 1: Parameters monitored ex post**

(a)	(b)	(c)	(d)	(e)	(f)	(g)	(h)	(i)	(j)	(k)
Monitoring period	Monitoring point No.	Parameters	Description of data	Monitored Values	Units	Monitoring option	Source of data	Measurement methods and procedures	Monitoring frequency	Other comments
3/1/2017 - 30/12/2017	1	PH _p	Net heat quantity supplied by the project HOB during the period <i>p</i> .	3,534	GJ/p	Option C	Logged data of net heat quantity supplied by the project HOB	Measurement methods which are using a heatmeter meet the industrial standards (host country or international standard). Monitoring data is the amount of heat supplied from the project HOB. This monitoring data is recorded in the data logger that is built into the heat meter. Electric data recorded on the data logger is input to the spreadsheet properly. In these monitoring activities, QA/QC be implemented. - In the case that heatmeter with verification is used, the verification validity for the heatmeter does not expire till the last date of the monitoring period. - If the heatmeter with the verification is not required in the industrial standard, uncertainty of the calibration data of the monitoring equipment meet the following conditions; - It is within accepted level of the verification. - It is within the accuracy level of industry standard requires. Required calibration frequency is the frequency which can be confirmed to be within the accuracy level of the requirement of industrial standard.	Measuring frequency: Continuously Recording frequency: Hourly	Trouble shooting procedure of missing data; Completed by the hourly minimum value (excluding abnormal value) of available recorded data during the monitoring period.
3/1/2017 - 30/12/2017	2	HMP _p	Total hours of the project HOB operation during the period <i>p</i>	11,410	hours/p	Option C	Identified by monitoring period	Total time from the start time of monitoring to the end time of monitoring	---	---

Table 2: Project-specific parameters fixed ex ante

(a)	(b)	(c)	(d)	(e)	(f)
Parameters	Description of data	Estimated Values	Units	Source of data	Other comments
RPC _{PJ,HOB}	Rated power consumption of the project HOB	1	kW	Catalog value provided by the manufacturer of the project HOB	
EF _{CO₂,grid}	CO ₂ emission factor of the grid electricity consumed by the project HOB	1.1030	tCO ₂ /MWh	The most recent value available at the time of validation is applied and fixed for the monitoring period thereafter. The data is sourced from CDM Mongolia unless otherwise instructed by the Joint Committee.	

Table3: Ex-post calculation of CO₂ emission reductions

Monitoring Period	CO ₂ emission reductions	Units
3/1/2017 - 30/12/2017	59	tCO ₂ /p

[Monitoring option]

Option A	Based on public data which is measured by entities other than the project participants (Data used: publicly recognized data such as statistical data and specifications)
Option B	Based on the amount of transaction which is measured directly using measuring equipments (Data used: commercial evidence such as invoices)
Option C	Based on the actual measurement using measuring equipments (Data used: measured values)

Monitoring Report Sheet (Calculation Process Sheet) [For Verification]

1. Calculations for emission reductions	Fuel type	Value	Units	Parameter
Emission reductions during the period p	N/A	59	tCO ₂ /p	ER _p
2. Selected default values, etc.				
CO ₂ emission factor of coal	Coal	0.0909	tCO ₂ /GJ	EF _{CO₂, coal}
Boiler efficiency of the reference HOB	N/A	0.533	-	η _{RE,HOB}
Boiler efficiency of the project HOB	N/A	0.610	-	η _{PJ,HOB}
3. Calculations for reference emissions				
Reference emissions during the period p	N/A	602	tCO ₂ /p	RE _p
Reference Emissions	N/A	602	tCO ₂ /p	
Net heat quantity supplied by the project HOB	N/A	3,534	GJ/p	PH _p
Boiler efficiency of the reference HOB	N/A	0.533	-	η _{RE,HOB}
CO ₂ emission factor of coal	Coal	0.0909	tCO ₂ /GJ	EF _{CO₂, coal}
4. Calculations of the project emissions				
Project emissions during the period p	N/A	543	tCO ₂ /p	PE _p
Project emissions (Fossil fuel consumption)	N/A	527	tCO ₂ /p	
Net heat quantity supplied by the project HOB	N/A	3,534	GJ/p	PH _p
Boiler efficiency of the project HOB	N/A	0.610	-	η _{PJ,HOB}
CO ₂ emission factor of coal	Coal	0.0909	tCO ₂ /GJ	EF _{CO₂, coal}
Project emissions (Electricity consumption)	N/A	16	tCO ₂ /p	
Electricity consumption of the project HOB	Electricity	14	MWh/p	EC _p
Total hours of the project HOB operation	N/A	11,410	h/p	HMP _p
Rated power consumption of the project HOB	N/A	1	kW	RPC _{PJ,HOB}
CO ₂ emission factor of the grid	Electricity	1.1030	tCO ₂ /MWh	EF _{CO₂, grid}

[List of Default Values]

CO ₂ Emission Factor of Coal used in HOBs	EF _{CO₂, coal}	unit
Default emission factor applied to Lignite in fuel according to "2006 IPCC Guidelines for National Greenhouse Gas Inventory"	0.0909	tCO ₂ /GJ

Boiler Efficiency of coal-fired HOB in Mongolia	η	unit
Boiler Efficiency of Reference the HOB	0.533	-
Boiler Efficiency of the Project HOB	0.610	-

Monitoring Report Sheet (Input Sheet) [For Verification]**Table 1: Parameters monitored ex post**

(a)	(b)	(c)	(d)	(e)	(f)	(g)	(h)	(i)	(j)	(k)
Monitoring period	Monitoring point No.	Parameters	Description of data	Monitored Values	Units	Monitoring option	Source of data	Measurement methods and procedures	Monitoring frequency	Other comments
1/1/2018 - 15/5/2018	1	PH _p	Net heat quantity supplied by the project HOB during the period <i>p</i> .	2,157	GJ/p	Option C	Logged data of net heat quantity supplied by the project HOB	<p>Measurement methods which are using a heatmeter meet the industrial standards (host country or international standard). Monitoring data is the amount of heat supplied from the project HOB. This monitoring data is recorded in the data logger that is built into the heat meter. Electric data recorded on the data logger is input to the spreadsheet properly. In these monitoring activities, QA/QC be implemented.</p> <p>- In the case that heatmeter with verification is used, the verification validity for the heatmeter does not expire till the last date of the monitoring period. - If the heatmeter with the verification is not required in the industrial standard, uncertainty of the calibration data of the monitoring equipment meet the following conditions; - It is within accepted level of the verification. - It is within the accuracy level of industry standard requires. Required calibration frequency is the frequency which can be confirmed to be within the accuracy level of the requirement of industrial standard.</p>	<p>Measuring frequency: Continuously Recording frequency: Hourly</p>	Trouble shooting procedure of missing data; Completed by the hourly minimum value (excluding abnormal value) of available recorded data during the monitoring period.
1/1/2018 - 15/5/2018	2	HMP _p	Total hours of the project HOB operation during the period <i>p</i>	6,430	hours/p	Option C	Identified by monitoring period	Total time from the start time of monitoring to the end time of monitoring	---	---

Table 2: Project-specific parameters fixed ex ante

(a)	(b)	(c)	(d)	(e)	(f)
Parameters	Description of data	Estimated Values	Units	Source of data	Other comments
RPC _{PJ,HOB}	Rated power consumption of the project HOB	1	kW	Catalog value provided by the manufacturer of the project HOB	
EF _{CO₂,grid}	CO ₂ emission factor of the grid electricity consumed by the project HOB	1.1030	tCO ₂ /MWh	The most recent value available at the time of validation is applied and fixed for the monitoring period thereafter. The data is sourced from CDM Mongolia unless otherwise instructed by the Joint Committee.	

Table3: Ex-post calculation of CO₂ emission reductions

Monitoring Period	CO ₂ emission reductions	Units
1/1/2018 - 15/5/2018	36	tCO ₂ /p

[Monitoring option]

Option A	Based on public data which is measured by entities other than the project participants (Data used: publicly recognized data such as statistical data and specifications)
Option B	Based on the amount of transaction which is measured directly using measuring equipments (Data used: commercial evidence such as invoices)
Option C	Based on the actual measurement using measuring equipments (Data used: measured values)

Monitoring Report Sheet (Calculation Process Sheet) [For Verification]

1. Calculations for emission reductions	Fuel type	Value	Units	Parameter
Emission reductions during the period p	N/A	36	tCO ₂ /p	ER _p
2. Selected default values, etc.				
CO ₂ emission factor of coal	Coal	0.0909	tCO ₂ /GJ	EF _{CO₂, coal}
Boiler efficiency of the reference HOB	N/A	0.533	-	η _{RE,HOB}
Boiler efficiency of the project HOB	N/A	0.610	-	η _{PJ,HOB}
3. Calculations for reference emissions				
Reference emissions during the period p	N/A	367	tCO ₂ /p	RE _p
Reference Emissions	N/A	367	tCO ₂ /p	
Net heat quantity supplied by the project HOB	N/A	2,157	GJ/p	PH _p
Boiler efficiency of the reference HOB	N/A	0.533	-	η _{RE,HOB}
CO ₂ emission factor of coal	Coal	0.0909	tCO ₂ /GJ	EF _{CO₂, coal}
4. Calculations of the project emissions				
Project emissions during the period p	N/A	331	tCO ₂ /p	PE _p
Project emissions (Fossil fuel consumption)	N/A	322	tCO ₂ /p	
Net heat quantity supplied by the project HOB	N/A	2,157	GJ/p	PH _p
Boiler efficiency of the project HOB	N/A	0.610	-	η _{PJ,HOB}
CO ₂ emission factor of coal	Coal	0.0909	tCO ₂ /GJ	EF _{CO₂, coal}
Project emissions (Electricity consumption)	N/A	9	tCO ₂ /p	
Electricity consumption of the project HOB	Electricity	8	MWh/p	EC _p
Total hours of the project HOB operation	N/A	6,430	h/p	HMP _p
Rated power consumption of the project HOB	N/A	1	kW	RPC _{PJ,HOB}
CO ₂ emission factor of the grid	Electricity	1.1030	tCO ₂ /MWh	EF _{CO₂, grid}

[List of Default Values]

CO ₂ Emission Factor of Coal used in HOBs	EF _{CO₂, coal}	unit
Default emission factor applied to Lignite in fuel according to "2006 IPCC Guidelines for National Greenhouse Gas Inventory"	0.0909	tCO ₂ /GJ

Boiler Efficiency of coal-fired HOB in Mongolia	η	unit
Boiler Efficiency of Reference the HOB	0.533	-
Boiler Efficiency of the Project HOB	0.610	-